Office of the Executive Engineer Dasarahalli Division,

Tender No: BBMP/EE/DD/TEN/05/12-13 Date: 29.09.2012 Item No: 23

SCHDULE-B

NAME OF WORK: Providing CC Surface at Deffence colony Cross roads in Ward No. 14 at T. Dasarahalli Sub-Division, Dasarahalli Zone.

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed the disposed earth to be leveled neatly after breaking of clods complete as per specifications.	Cum	178.92	90.00	Rupees Ninety Only
2	Plain cement concrete 1:3:6 mix with crushed stone aggregates 40m nominal size mechanically mixed, placed in foundation and compacted by vibration including curing for 14days complete as per specifications.	Cum	25.56	3809.00	Rupees Three Thousand Eight Hundred Nine Only
3	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320kgs,with 20mm and down size graded granite metal Coarse aggregates @ 0.69cum and fine aggregates @0.46cum with superplastisiser @ bits confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for R.C.C beams, columns of all sizes in foundation plinth and Superstructure ground floor level for roof slabs, staircase, lintels columns, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	67.10	5390.00	Rupees Five Thousand Three Hundred Ninety Only
4	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	q	27.00	7535.00	Rupees Seven Thousand Five Hundred Thirty Five Only
5	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour complete as per specifications.	Sqm	454.40	181.00	Rupees One Hundred Eighty One Only

Signature of the Contractor

Executive Engineer

6	Providing & Laying Reinforced cement precast slabs of n. . M20 Using 20mm & down size graded granite metal using HYSD 10mm dia steel @100mm c/c both ways & complete as per specfications.	Sqm	127.80	2052.00	Rupees Two Thousand Fifty Two Only
7	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading	Cum	140.00	81.00	Rupees Eighty One Only

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,